## Port Ludlow Drainage District – Inventory Listing November 2017

Facilities Installed by District (shown on attached MAPS in RED)				
	Facility	Location	Maintenance	
1	North Bay Condos No. 2 Conveyance	North Bay Condos No. 2	Storm pipe	
_	System	south of Oak Bay Road	cleaning/inspection	
2	Area 7 Detention Pond/Bioswale	Detention pond north	Routine vegetation	
-	/ ii cu / Beterition i ona/ Biosware	of Oak Bay Road	management	
3	Warbler Lane	East of Warbler Lane	Vegetation maintenance	
,	Wallier Lane	cul-de-sac	Vegetation maintenance	
4	Machias Loop Conveyance	Parcel Drainage	Inlet inspection	
7	Improvement	easement east of	mice inspection	
	Improvement	Machias		
5	WWTP Ditch and Culvert	Easement PLA west of	Ditch maintenance, culvert	
5	WWW Diten and Curvert	WWTP	inlet inspection	
6	Cascade Lane Flood Abatement	Easement between	Inlet	
U	Cascade Lane Flood Abatement	Olympic Lane and	inspection/maintenance,	
		Cascade Lane, LMC	vegetation maintenance	
		greenbelt	Vegetation maintenance	
7	Pope Way Outfall	East of Condon Lane at	Inspect/clean inlet catch	
,	Tope way Outrain	intersection of Pope	basin. Inspect outfall.	
		Way and Condon Lane	Potential debris removal at	
		Way and Condon Lanc	beach outfall.	
8	Trader Lane Improvements	South of Trader Lane	Vegetation	
0	Trader Lane improvements	cul-de-sac	maintenance/inlet inspection	
9	Fleet Drive French Drain	Greenbelt north side of	French drain vegetation	
5	Tiect Brive French Brain	Fleet Drive between	maintenance	
		Pathfinder Lane and	maintenance	
		Adventurer Lane		
10	Upper Baldwin Drainage	West of Oak Bay Road	Vegetation maintenance,	
10	Improvement	and Baldwin Lane	Monitor/Clean Catch Basin	
	improvement	intersection	inlets	
11	Oak Bay Road to Montgomery Lane	Oak Bay Road to	Vegetation maintenance	
	Ditch	Montgomery Lane	(adjacent property owner).	
		south of Baldwin	Repair/rehabilitation of rock	
			lining and check dams.	
12	Libby Court Outfall	Montgomery Lane	Annual inspection of outfall.	
		north of Libby Ct to	Potential maintenance –	
		beach	remove sediment from catch	
			basin.	
13	Adventurer Lane Cut-off trench	North end Adventurer	French drain vegetation	
		Lane cul-de-sac	maintenance	
14	McCurdy Lane Cutoff Trench	Easement between	French drain vegetation	
	,	Pioneer Drive West and	maintenance	
		McCurdy Lane		
15	Jackson- Foster French Drain	Easement between	French drain vegetation	
	-	Jackson Lane and Foster	maintenance	
		Lane		
16	Foster Lane Drainage Improvement	North end Foster Lane	Pipe inlet cleaning	
_			,	
		cul-de-sac		

Other Area Maintenance Activities (shown on attached MAPS in GREEN)					
	Facility	Location	Maintenance		
1	Ludlow Cove II	Catch Basins	Clean CBs (District obligation begins after construction of all properties within the development are completed.)		
2	Waterhouse Lane - Developer installed detention pond and outlet structure	West end Waterhouse Lane	Vegetation maintenance, storm pipe cleaning/inspection		
3	Bird Lane cul-de-sacs	East ends of Hummingbird Court, Wren Court, Sparrow Lane, Goldfinch Lane, Falcon Lane, Mockingbird Lane	Vegetation maintenance		
4	Drainage easement 191 and 201 Condon Lane	Plat drainage easement 191 and 201 Condon Lane	Inlet maintenance		
5	Libby Court Ditch	South end of Libby Court	Vegetation maintenance		
6	Montgomery Court Outfall	Between 70 and 120 Montgomery Court	Outfall inspection		
7	North Montgomery Court Outfall	East side of Montgomery Court cul-de-sac	Outfall inspection		

	Areas to Watch				
	(shown on at	tached MAPS in BLUE)			
	Location	Notes			
1	Marina Outfall	Culvert #87. 36-inch from Oak Bay			
		Road. Evaluate condition of outfall			
		periodically.			
2	South Montgomery Lane	Citizen complaint 2012. Drainage			
		from west side of Montgomery			
		Lane sheet flows into yard (621			
		Montgomery Lane). Existing ditch			
		on west side of Montgomery Lane			
		intercepts drainage from the west			
		and carries it to a culvert			
		approximately 160 feet north of			
		621 Montgomery Lane to a			
		dedicated drainage easement.			
		Three alternatives discussed at site meeting.			
		(1) Install a slotted drain across the			
		driveway with discharge to the			
		ditch on the west side of			
		Montgomery Lane			
		(2) Install a ditch within County			
		right-of-way on the east side of			
		Montgomery Lane with a potential			
		point of discharge through the			

Reserve Area to the south end of the cul-de-sac to the WWTP ditch, (3) Install a slotted drain across the driveway with a piped conveyance system to the WWTP ditch. This issue with runoff from the road entering 621 Montgomery Lane is an issue that affects many properties in the District that are located on the downhill side of the road system. These issues are typically handled by the property owner. 3 South Condon Lane Citizen complaint 2010 and 2015. Existing drainage easement between 191 and 201 Condon Lane directs the majority of the runoff from Condon Lane, south of Pope Way to Admiralty Bay. The ditch on the west side of Condon Lane from 210 Condon Lane to 192 Condon Lane slopes north to direct runoff to the drainage easement. Jefferson County installed a small berm across Condon Lane at approximately 192 Condon Lane in 2010 in response to the homeowner complaint. Runoff from the east side of Condon Lane (201, 211 and 221) sheet flows to the east to Admiralty Bay. In 2010 Commissioners informed the property owner that there is no viable solution to his problem other than for him to install a curtain to deal with runoff coming onto his property and that the District would not assist with this individual effort. In 2015 the Commissioners expressed interest in directing flow from the cul-desac to the South. The undeveloped property at the south end of the cul-de-sac belongs to Olympic Water and Sewer and is not commonly held property. This issue with runoff from the road entering 211 Condon Lane is an issue that affects many properties in the District that are located on the downhill side of the road system. These issues are typically handled by the property owner.

4	Drainage easement 191 and 201 Condon Lane	Evaluate outfall location and condition.
5	Oak Bay Road Culverts (north and south of Baldwin Lane)	Several County owned culverts from the road-side ditch on the west side of Oak Bay Road north and south of Baldwin Lane discharge across the road to the east side of the road. The east road embankment does not contain a ditch. The stormwater discharge sheet flows across private property. The District has asked the County to block the culverts to ensure that the flow in the ditch reaches the Libby Court outfall system as intended. The County has indicated that they want to leave the culverts in place to prevent overflow from the ditch and water onto the roadway. Private property owners are impacted by the culvert discharge.
6	North Montgomery Court Inlet	The inlet to the North Montgomery Court Outfall system should be evaluated periodically.



